

Pro-Flow Gutters LLC

Quality Continuous Gutter Installation

Name: _____ Notes: _____

Phone: _____

Address: _____

Work Scope

1. Removal and recycling of existing gutters and downspouts.
2. Install new aluminum 5K or 6K gutters with hidden hangers and screws every two feet and or every rafter tail.
3. Install new aluminum 2x3, 3x4 or 3" round downspouts.
4. Installing of new gutters and downspouts will be replaced in their existing location unless otherwise directed in the drawing and or discussed.
5. Corners are hand mitered and sealed with a commercial-grade gutter sealant. (Vulkem)
6. After installation, there may be places of old paint lines on the fascia and siding where the existing gutter or downspout was located.
7. Small damage may occur to the ground, plants, shrubbery, and decks due to the positioning of ladders where needed. With that being said, we always do our best to be careful!
8. A thorough clean-up will be done upon completion of the job. At the same time, we are doing our best throughout the job to keep it clean. There could be small debris left behind.
9. Lifetime warranty on workmanship for the life of the gutters.
10. 20-year manufacturer warranty by Mastic on gutters, no chip, peel, fade, or expanse and contraction. Don't forget to register your warranty at www.mastic.com/warranty.

Prior to Work

1. Homeowner's responsible for the following precautions and preparation for this gutter project.
2. Keep children and pets inside and away from the areas being worked on at all times! To prevent any bodily damage from debris or tools.
3. Remove items away from the perimeter of the working area.
4. Covering items that may get falling debris or dust.
5. Moving vehicles from the driveway or places where parking is needed.
6. Power will be needed out front within 100ft of the gutter truck if possible.
7. Confirm and sign the bid sheet.



Servicing:

Snohomish, King & Skagit County's

Phone & Text: 425-415-6773

Email: proflowgutters@gmail.com